

## NOTES:

- MANHOLE TO BE SET ON CONCRETE BASE AND BASE TO BE ONE POUR.
  FOR VITRIFIED CLAY PIPE, CONCRETE SHALL BE POURED TO NEXT EXISTING JOINT (BOTH SIDES OF MANHOLE).
- PIPE OPENING SHALL BE PRECAST BY MANUFACTURER.
- FLOW SHALL BE MAINTAINED DURING CONSTRUCTION. MINIMUM OF 4000 PSI CONCRETE REQUIRED.

- THE CONTRACTOR SHALL PROVIDE A MINIMUM 6" COMPACTED #57 STONE BASE. INVERT TO BE BUILT FROM PROPOSED PIPE TO EFFLUENT PIPE, ACCORDING TO DETAIL ON INVERTS.



SAB APPROVED BY: KFM DRAWN BY:

DATE: 10/23/2018

## DOGHOUSE MANHOLE INSTALLATION OVER EXISTING SEWER MAIN

DURHAM COUNTY, NORTH CAROLINA **ENGINEERING DEPARTMENT** 

SCALE: NTS

DETAIL NO. **DUCO - 012**