



TYPICAL CROSS - SECTION

NOTES:

1. INVERT MATERIAL SHALL BE CONCRETE CAST IN PLACE WITH A SMOOTH FINISH.
2. WIDTH OF INVERT SHALL MATCH INSIDE DIAMETER OF INCOMING AND OUTGOING PIPES.
3. BRICK INVERT SHALL BE FORMED AS SHOWN.
4. ALL INVERT ELEVATIONS SHALL BE AS SHOWN ON APPROVED CONSTRUCTION PLANS.
5. BENCHES TO BE BUILT OUT OF CONCRETE, MORTARED BLOCK OR BRICK. STONE IS NOT ACCEPTABLE.



SAB
APPROVED BY:

KFM
DRAWN BY:

DATE: 10/23/2018

SANITARY SEWER MANHOLE INVERT

DURHAM COUNTY, NORTH CAROLINA
ENGINEERING DEPARTMENT

SCALE:
NTS

DETAIL NO.
DUCO - 004